ANDHRA PRADESH SOLAR POWER CORPORATION LIMITED

From: To:

The Superintending Engineer/Civil Flat No. 501, 5th Floor Garuda Enclave, Beside TG Plaza, Tadepalli, Guntur Dist.

As per list

Enquiry No. 09 /2020-21/SE/APSPCL/ Thondur / DPR/D.No. 167/20, dt. 17 -07-2020

Sir,

Sub: APSPCL - Thondur Ultra Mega Solar Park (500 MW) - Preparation of Detailed Project Report for establishment of solar Project at Mallela, Bhuchupalli, Thondur villages of Thondur Mandal of YSR Kadapa - Sealed Quotations are invited - Regarding.

The Andhra Pradesh Solar Power Corporation is proposing to establish 500 MW Solar Project at Mallela, Bhuchupalli, Thondur villages of Thondur Mandal of YSR Kadapa. The proposed project site is located at a distance of about 19.60 KM from Pulivendula.

Sealed quotations are invited from the reputed consultancies who are having experience in preparation of Detailed Project Reports. The sealed quotations shall be submitted on or before 3.00 PM on 30th July 2020 to the Superintending Engineer, Civil, APSPCL, Flat No. 501,5th Floor, Garuda Enclave, Beside TG Plaza, Tadepalli, Guntur Dist. and the same will be opened in the chambers of the Chief Operations Officer on 30th July 2020 @ 4.00 PM.

The sealed covers shall be superscripted with "Quotation for Preparation of Detailed Project Report for establishment of Solar Project at Mallela, Bhuchupalli, Thondur villages of Thondur Mandal of YSR Kadapa". The quotation shall be in accordance with the terms and conditions specified in the Detailed Tender Specification. The details may also be obtained from www.apspcl.ap.gov.in

It is requested to furnish your lowest offer in a sealed cover.

Encl.: 1. Detailed Tender Specification along with price schedule

Yours faithfully, Sd/-Superintending Engineer/Civil APSPCL – Tadepalli

Copy to Notice Board

Copy submitted to the E.E/T to C.M.D/APSPCL for kind perusal of CMD

Copy submitted to V.C & M.D/NREDCAP/Tadepalli for favour on information*

Copy submitted to C.E/Civil/General, C&I, Hydel/APGENCO/Vidyut Soudha/Gunadala*

Copy to the Deputy Executive Engineer/Electrical/APSPCL/Kurnool*

Copy to the Deputy Executive Engineer/Civil/APSPCL/Kadiri*

Copy to the Assistant Executive Engineer/Civil/

*for displaying on the notice boards

DETAILED TENDER SPECIFICATION

1. **SCOPE OF TENDER:**

Preparation of Detailed Project Report for establishment of solar Project at Mallela, Bhuchupalli, Thondur villages of Thondur Mandal of YSR Kadapa of Andhra Pradesh covering all the aspects as required as per the standard format for solar projects/parks for submission to statutory authorities like MNRE, SECI, Government of Andhra Pradesh etc.,

2. **SCOPE OF WORK:**

The scope of services shall include site visit, collection of required data, study of land topography, soil investigation, conducting engineering surveys, preparation of plot plan duly incorporating all components of solar project, planning, designing, detailing of various components like Solar panel arrays, Sub pooling stations, cable racks, transformers, inverters, internal roads, drainage arrangements, trenches, water supply and distribution arrangements, evacuation corridors, street lighting, telecommunication networks, common building infrastructure - preparation of quantity and cost estimates, scheduling of project, submission of DPR.

The scope of the work shall be divided as per mile stones given below.

Mile Stone 1 - Preparation of Plot plan

- Site visit, collection of data on various infrastructure requirements, Study of land topography, assessing un-usable areas, obtaining levels for preparation 5m contours, preparation of project plot plan duly indicating solar project plots, roads, drains, planning of Pooling stations and internal evacuations, street lighting, water storage tanks and distribution network, common control building, administrative building, storage sheds, fire station building, pumping stations, meteorological station, watch towers, area for township and all other facility that are generally required for solar parks.
- Conducting geotechnical investigations and soil resistivity at various locations as directed by APSPCL.
- Conducting ground water study and ground water analysis, identifying nearby water sources for cleaning of solar panels.
- Review of environmental issues, highlighting climatic, environmental and seismic conditions which can affect the progress, life and performance of solar parks.
- Abstract cost of Land, water, civil and evacuation infrastructures.

Mile Stone 2 - Detailed Engineering

- Conducting detailed survey for internal roads, drains, water supply distribution lines and cable trenches.
- Study, Design and Engineering of various components of solar projects like solar panels, inverters, transformers, cables, preparation of project layout plans.
- Foundations, Module Mounting Structures.
- Furnishing design basis reports, design calculations, concept drawings of all components of Solar Power Projects.
- Furnishing abstracts of Solar Project Costs.

Mile Stone 3 - Finalization of Detailed Project Report

- Furnishing financial analysis including estimates of revenue and operating costs, profitability analysis, projected balance sheet and cash flow.
- Furnishing Project implementation schedule.
- Chapter wise compilation of Detailed Project Report.
- Submission of draft copies (Two) of DPR for APSPCL comments.
- Attending to the remarks/ comments/ suggestions of APSPCL and incorporation of the same in the final DPR.
- Submission of final DPR along with drawings in A-0 size.

3 TIME SCHEDULE

The entire scope of consultancy services including designs and drawings shall be completed within four months from the date of receipt of work order. However, the milestone wise scheduled completion date shall be as below:

- I. Mile Stone 1 15 days from receipt of purchase order.
- II. Mile Stone 2 25 days from receipt after acceptance of mile stone I.
- III. Mile Stone 3 5 days from receipt on acceptance of mile stone II.

4 TERMS OF PAYMENT

Payment shall be made within seven days from the date of submission of the bill. Payment schedule shall be as follows:

- I. On completion of Mile Stone 1 30 %
- II. On completion of Mile Stone 2 50 %
- III. On completion of Mile Stone 3 20 %

5 RECEIPT OF TENDERS:

The sealed bids shall be submitted on or before **3.00 PM 30**th **July 2020** to the Superintending Engineer, Civil, APSPCL Flat No. 501, 5th Floor, Garuda Enclave, Beside TG Plaza, Tadepalli, Guntur Dist., and the same will be opened in the chambers of Chief Operations Officer / APSPCL **at 4.00 PM**.

The Tender cover shall contain the superscriptions "Preparation of Detailed Project Report for establishment of Solar Project at Mallela, Bhuchupalli, Thondur villages of Thondur Mandal of YSR Kadapa"

6 VALIDITY:

The tender shall be valid for a period of 60 days from the date of opening of the tender.

7 PRICES:

The prices quoted for "Preparation of Detailed Project Report" shall be firm and inclusive of all except GST which will be paid as per actual.

8 STANDARDS OF DPR:

The Detailed Project Report shall be strictly prepared as per the latest guidelines if any for solar projects. The designs shall be carried out as per the relevant Bureau of Indian Standards.

9 PENALTY:

In the event of any delay beyond the stipulated dates given in clause No.3, the corporation reserves the right to recover from the supplier a sum equivalent to 0.5% of Purchase Order value for each week of delay and part thereof subject to a maximum of 5% of the total value of order.

10 <u>EMD</u>:

0.5% of the quoted value in the form of Demand Draft drawn in favour of Managing Director /APSPCL. The EMD shall be paid along with the offer. The offers without EMD will not be accepted.

11 SECURITY DEPOSIT:

The EMD of the successful bidder will be retained with APSPSCL and adjusted towards the Security Deposit. The successful bidder shall deposit the balance security deposit @ 2.0% of the quoted price to make a total of 2.5% of quoted value in the form of Demand Draft /Bank Guarantee in favour of Managing Director/APSPCL within a week from the date of receipt of Purchase Order. The Security Deposit will be released after approval of final DPR.

12 SUBMISSION OF REPORT:

- a) Two (2) copies of Draft DPR along with two sets of draft drawings in A-1 size and one soft copy of DPR and drawings.
- b) Five (5) sets of final DPR with A-0 size drawings and 2 sets of soft copies of the report in Microsoft word & Excel format and drawings in Auto cad format and PDF format.

13 ARBITRATION:

All and any disputes or differences shall be decided by courts or tribunal situated in cities of Amaravati only. No suit or other legal proceedings shall be instituted elsewhere.

14 GENERAL:

Village combined map containing the survey numbers, extent of land etc., will be given to the successful bidder. No facilities of any kind will be provided by APSPCL in carrying out investigations. The consultant shall make his own arrangements for transportation, conveyance or accommodation etc., during their visits to the site or to APSPCL office, or other statutory offices. Carrying out soil investigations shall be done in close co-ordination with Revenue Department. The copies of Firm registration, Experience of similar works executed, GST registration and PAN card shall be furnished along with your offer.

Sd/-SUPERINTENDING ENGINEER/CIVIL APSPCL - TADEPALLI

SCHEDULE OF WORK:

S.No.	Quantity	Description of work	Lump Sum Amount in	
			Figures RsPs.	Words
1	One Project	Preparation of Detailed Project Report for		
		establishment of 500 MW Solar Project in		
		Mallela, Bhuchupalli, Thondur villages of		
		Thondur Mandal of YSR Kadapa of Andhra		
		Pradesh as per the detailed specification		

TOTAL (in Fig. & Words):

Sd/-SUPERINTENDING ENGINEER/CIVIL APSPCL - TADEPALLI