ANDHRA PRADESH SOLAR POWER CORPORATION PRIVATE LIMITED (A J V COMPANY OF GOVT OF ANDHRA PRADESH AND GOVT OF INDIA)

BIDDING DOCUMENT (SINGLE PART BID)

FOR THE WORK OF

Name of work: APSPCL - CSR - Supply, Erection, Testing and Commissioning of RO plant of 2000 lit/hr capacity

Commissioning of RO plant of 2000 lit/hr capacity including construction of plant room at Diguvagottivedu Village, Chinna Mandem Mandal of YSR Kadapa District,

A.P.

Tender Notice No. 11/2020-21/SE/C/APSPCL/F.Dkt/D.No.660/20, Dt.10.02.2021

ANDHRA PRADESH SOLAR POWER CORPORATION PRIVATE LIMITED <u>CSR Works</u>

TENDER NOTICE Tender Notice No. 11/2020-21/SE/C/APSPCL/F.Dkt/D.No.660/20, Dt.10.02.2021

1.	Department Name	Andhra Pradesh Solar Power Corporation Private Limited (A J V Company Of Govt. Of Andhra Pradesh And Govt. Of India)				
2.	Circle/Division Name	Superintending Engineer / Civil / APSPCL / Guntur				
3.	Tender Notice No.	Tender Notice No. 11/2020-21/SE/C/APSPCL/F.Dkt/ D.No.660/20, Dt.10.02.2021				
4.	Name of Work	APSPCL - CSR - Supply, Erection, Testing and Commissioning of RO plant of 2000 lit/hr capacity including construction of plant room at Diguvagottivedu Village, Chinna Mandem Mandal of YSR Kadapa District, A.P.				
5.	Estimated Contract Value (Approximately)	Rs.4,98,286/- (Rupees Four Lakh Ninety Eight Thousand Two Hundred and Eighty Six Only)				
6.	Period of Contract	One Month				
7.	Form of Contract	L.S				
8.	Tender Type	Open				
9.	Tender Category	Works				
10.	Tender Schedule Cost	Rs.336/- (Rupees Three Hundred and Thirty Six only)				
11.	Bid Security (EMD)	Rs.7,500/- (Rupees Seven Thousand and Five Hundred Only)				
12.	Bid Security Payable to	By way of DD drawn on any nationalized bank in favour of Managing Director/ APSPCL/ Guntur.				
13.	Last date for receipt of application for tender schedule.	Up to 24.02.2021, 03.00 P.M				
14.	Sale of tender schedules	Up to 24.02.2021, 05.00 P.M				
15.	Last date for receipt of tenders	25.02.2021, 3.00 P.M				
16.	Bid Submission	The intending tenderer/Contractors have to submit their tenders in the Chamber of Superintending Engineer/Civil/APSPCL.				
17.	Bid Validity	180 days from the date of opening of the Bid				
18.	Opening of tenders	25.02.2021, After 5.00 P.M				
19.	Eligibility Criteria	1. Registration (i) The intending tenderer should have posses minimum Class V & above in any State/Central Govt. or any State/Central PSU etc. (ii) Registration under process shall not be accepted.				
20.	Place of Opening of Tenders	In the chambers of Superintending Engineer/Civil/ APSPCL, office of the Technical Wing, Flat no. 501, 5 th Floor, Garuda Enclave, Beside TG Plaza, Tadepalli, Guntur Dist - 522 501. E-Mail: apspcl@ap.gov.in				
21.	Procedure for bid submission	a) Intending tenderers may obtain tender schedules from office of Superintending Engineer/Civil/APSPCL/Tadepalli/Guntur in person or through their authorized agents. The tenderers shall apply for tender schedules along with the separate DDs in favour of Managing Director/APSPCL/Tadepalli/Guntur payable at Guntur for cost of tender schedule and EMD to the undersigned.				

22.	Statutory Requirements	The tenderer shall fulfill the following statutory requirements.				
		 a) <u>Labour Rules and Regulations</u> The tenderer shall comply with all statutory labour rules and regulations for EPF, GIS/ESI, Labour cess, Contract labour rules, Workmen compensation etc., as may be applicable. b) <u>GST</u> 				
		The tenderer should have registration under GST in the state of Andhra Pradesh from concerned department. Applicable GST as on date is 18% of total value of the contract and the rates quoted shall be exclusive of GST.				
23.	Other Payments to be made	Apart from the Bid Security (EMD) the tenderer shall be liable to pay the cost of tender schedule.				
24.	Documents to be submitted to the Tender inviting	All the bidders shall submit the scanned copies of the following documents along with the tender schedule.				
	authority.	 DD for EMD amount - This will be the primary requirement to consider the bid responsive Mandatory. Contractor registration certificates - Mandatory. Registration copies of EPF, ESI/Insurance & GST. 				
		Note: 1) The tenderer is liable to be disqualified, if he is found to have mislead or furnished false information in the forms / Statements / Certificates submitted in proof of qualification requirements and record of performance such as abandoning of work, not properly completing of earlier contracts, inordinate delay in completion of works, litigation history, financial failures and or participated in the previous tendering for the same work and has quoted unreasonable high price etc.				
		2) Even while executing the work, if found that the contractor had produced false/fake certificates, he will be black listed and the contract will be terminated and his Bid security will be forfeited and work will be carried out through other agency at his cost and risk.				
25.	Other relevant information	 APSPCL reserves the right to award even part work or to cancel the tenders without assigning any reasons thereof. No tender schedule will be sent by post. The cost of tender schedules once paid will not be refunded under any circumstances. 				

Sd/-SUPERINTENDING ENGINEER/CIVIL

To

The Bidders through notice board / APSPCL website.

Copy to the:

- 1) Notice Board.
- 2) The Executive Engineer/Tech to the Chairman & Managing Director/APSPCL for information.
- 3) The Deputy Executive Engineer/Electrical/APSPCL/Kurnool for information.
- 4) The Deputy Chief Controller of Accounts/APSPCL/Guntur for information.
- 5) The Deputy Executive Engineer/Civil/APSPCL/Kadiri for information.
- 6) The Deputy Executive Engineer/Civil/APSPCL/ Mylavaram for information.
- 7) The Chief Executive Consultant/Electrical/APSPCL/Kadiri for information.

DETAILED TENDER NOTICE

1. Sealed Tenders will be received by the **Superintending Engineer/Civil**, APSPCL, Tadepalli, Guntur, up to **3.00 PM on 25.02.2021** for the work of "APSPCL - CSR - Supply, Erection, Testing and Commissioning of RO plant of 2000 lit/hr capacity including construction of plant room at Diguvagottivedu Village, Chinna Mandem Mandal of YSR Kadapa District, A.P." **The tenders will be opened by the Superintending Engineer/Civil**, **APSPCL 5.00 PM onwards on 25.02.2021 in his chambers**.

If the tender opening day happens to be a holiday the tenders will be opened at the same timings mentioned above on the next working day. The tenderers or their authorized agents are expected to be present at the time of opening of tenders.

Intending bidders can contact office of the Superintending Engineer/Civil/APSPCL/Guntur for any clarification/ information on any working day during working hours

2. Earnest Money Deposit:

Each bidder must pay Bid Security i.e., Earnest Money Deposit of Rs.7,500/-(Rupees Seven Thousand and Five Hundred Only) while submitting their bids. The EMD shall be paid by way of DD drawn on any nationalized bank in favour of Managing Director/APSPCL and payable at Tadepalli.

- i. The Earnest Money Deposit will be refunded to the unsuccessful tenderer after intimation of the rejection of the tender or at the expiration of 180 days from the date of tender whichever is earlier.
- ii. The Earnest Money will be retained in the case of successful tenderer and will not carry any interest. It will be dealt with as provided in the tender.
- iii. Tenderers are not permitted to withdraw their or his offer once made for a period of 180 days after the opening of the tenders and in the event of such tenderers withdrawing their tenders' within 180 days after opening of tenders, the Earnest Money deposited by him/them will be forfeited by the APSPCL
- 2.1 In addition to the EMD, the balance amount of total up to 5% of the value of contract shall be paid by the successful tenderer as security deposit by way of Bank Guarantee/Demand Draft from Nationalized Bank approved by APSPCL as per proforma appended at the time of entering into the agreement. The above security deposit shall be furnished within fifteen (15) days from date of receipt of award. Further, 5% of the value of work done will be recovered from the running bills for the due fulfillment of the contract.

The Security deposit (including EMD) will be refunded to the contractor after satisfactory completion of performance guarantee period as all defects shall have been made good according to the true intent and meaning thereof. The guarantee period commences from the date of completion of the work in all respects satisfactorily. These amounts will not bear any interest.

The retention amount which is recovered from the running bills shall be released from final bill. These amounts will not bear any interest.

2.2 Failure to enter into the required agreement or to make the security deposit as defined in the above paragraphs shall entail forfeiture of the earnest money deposit. The written agreement to be entered in between the contractor and the APSPCL shall be the foundation of the rights of both the parties and the contract shall not be deemed to be complete until the agreement has first been signed by the contractor and then by the proper officer authorized to enter into contracts on behalf of APSPCL.

2.3 The work shall be commenced from the dates specified by APSPCL, otherwise EMD will be forfeited.

If the successful tenderer fails to sign the agreement or otherwise commit default, the APSPCL shall have the right to recover damages according to law apart from forfeiting the earnest money deposit.

3. **Period of contract: 1 Month**

3.1. **Programme of work**

The attention of the tenderer is directed to the contract requirements as to the time of beginning the work, the rate of progress and the dates for the completion of the whole work and its several parts.

The programme of work to be done from time to time is indicated below. However, the Executive Engineer / Engineer-in-charge of the work will decide the priority of various items of work and their location and direct the successful tenderer for execution so as to complete the entire work as required.

The date of commencement of this work will be the date on which the site is handed over to the Contractor. The agreement shall be concluded before the site is handed over to the contractor or before he draws any materials.

Further, it shall also be noted by the tenderer, if on any account, the work gets dislocated due to the site being not available for work on any day or due to any other reason, it is not binding on the APSPCL to pay any compensation to the contractor, but the corresponding extension of time will be granted to the contractor.

The construction programme for the works envisaged in the specification is indicated below:

S.No.	Period after date of commencement	Cumulative Percentage of the work to be completed based on contract amount	Remarks
(1)	(2)	(3)	(4)
1.	1 months	100 %	

The periods entered in column (3) for the purpose of defining the rate of progress may be altered by the Engineer-in-charge or appropriate authority authorized by APSPCL to suit the requirements of project completion.

If, due to any other reason beyond the control of the contractor, the progress is slow during any period indicated above, the same shall be made up in subsequent periods and the programme shall be complied within minimum possible time.

The Executive Engineer / Engineer -in-charge shall direct the sequence and pace of the parts of the work and the contractor shall comply with them. Payment will be effected as per actual work completed and based on the approved mode of payment.

4. Penalty: Action as per clause 60 and 61 of PS to APSS will be taken by the Executive Engineer / Engineer-in-charge if the contractor fails to adhere to the above programme of work.

Due to what so ever reasons, if work gets extended beyond the contract period, an amount equivalent to 5% of running account bill will be recovered

in the extended period of contract from the running account bills and release or forfeiture of this in part or full will be dealt as per the approval of competent authority of APSPCL.

5. The **Superintending Engineer/Civil/APSPCL**, or other sanctioning authority reserves the right to reject any tender in full or part or all the tenders without assigning any reason there for. The quoted percentage shall be binding on the tenderer even if the **Superintending Engineer/Civil/APSPCL** awards part of the work.

6. TAXES, DUTIES, TOLLS AND SEIGNIORAGE:

The contractor shall, unless otherwise specially stated in the tender notice and subsequently on this basis in the contract, be responsible for the payment wherever payable of all import duties, octroi duties, seigniorage, quarry fees etc. on all materials and articles that he may use Seignorage and local cess charges payable on the materials used by the tenderer in the work will be recovered at rates fixed by competent authority from time to time from the contractor's bills and the same will be remitted to Mines & Minerals Department.

All taxes, duties, seignorage and local cess charges, Turnover etc, except GST, EPF, GIS & Labour Cess (Labour cess will be recovered and remitted as TDS as per the building and other construction welfare cess act 1996) payable to the Govt./Quasi Govt.Bodies at the rates as on the date of opening of tender are deemed to be included in the quoted prices. The applicable GST as on date will be paid extra on submission of GST invoice. The payment of GST is the responsibility of the contractor. Seignorage on metal, sand, gravel etc., and local cess will be recovered at rates fixed by competent authority from time to time from the contract bills. However, Seignorage charges will not recovered if the contractor submits the proof of payment of Seignorage charges to the concerned department. Statutory variations in the applicable rates or newly introduced taxes/duties, Seignorage and local cess will be to APSPCL account subject to the condition that the work has to be completed as per the time schedule stipulated in the contract/agreement.

The percentage less/excess on ECV quoted for the subject work shall be excluding **GST, EPF, GIS, & Labour Cess. EPF & GIS** will be reimbursed by APSPCL on production of proof of actual remittances made and subject to the satisfaction of Engineer-in-Charge that the said contribution done is only for the workers employed on this work. Labour cess will reimbursed to the contractor as per actual on production of proof of payment as per the building and other construction welfare cess act 1996. APSPCL will not reimburse any excess payment made by the contractor for any of the above due to mis-interpretation of law or any other reason.

No GST will be collected from the contractor for the materials supplied by the APSPCL at free of cost.

Notwithstanding anything contained in Section 10 of the Indian Tariff Act, of 1894, the rates for item involving the use or supply of articles obtained by the contractor from outside India shall remain unaffected by any changes that may be introduced in the Customs duties.

Other taxes and duties levied by the Central/State Govt. prevailing as on the date of opening of tenders shall be to the contractor's account and the percentage less/excess on ECV value quoted shall be inclusive of them. Any increase in taxes and duties shall be to APSPCL's account. If there is any decrease in taxes and duties, credit shall be given to APSPCL to that extent.

The APSPCL will not however be responsible for payment any other tax made by the contractor under misapprehension of law.

7.0 **DEFECT LIABILITY**

7.1 The contractor shall be responsible to make good and remedy at his own cost within such a period as may be stipulated by the Engineer-in-charge any defect observed during the course of execution or which may develop or may be noticed before the expiry of the period mentioned in the Guarantee clause on intimation of which has been sent to the contractor within seven days of expiry of the said period by a letter sent by hand or Registered post.

8.0 **GUARANTEE**

- 8.1 The contractor shall guarantee that all items executed by him shall be free from all defects and workmanship up to completion of work in all respects.
- 8.2 APSPCL shall also be entitled to recover any losses direct or indirect incurred due to non-fulfillment of contractual commitment in this regard.
- 8.3 The Guarantee period shall be 6 months from the completion of the works in all respects.

TECHNICAL SPECIFICATIONS

1.00 GENERAL

This specification is to cover preparation of general arrangement, construction as well as Fabrication drawings, supply of all labour as well as materials and construction of all civil, structural works for the proposed Construction of "APSPCL - CSR - Supply, Erection, Testing and Commissioning of RO plant of 2000 lit/hr capacity including construction of plant room at Diguvagottivedu Village, Chinna Mandem Mandal of YSR Kadapa District, A.P." promoted by M/s. Andhra Pradesh Solar Power Corporation Private Limited.

2.00 SCOPE OF WORK:

In general broad scope of work consists of the following:

- a) Construction of 10 ft X 12 ft size of 8'6" height room for RO Water plant system with Load bearing construction.
- b) Supply, erection, testing and commissioning of 1000 LPH Reverse Osmosis (RO) Water plant with all suitable equipment, material and instruments & controls.
- c) Drilling of 4" size bore well with necessary casing pipe.
- d) Supply, erection and testing of 3 HP fifteen stages submersible pump.

The work shall complete in all respects under this specification shall include but not limited to the following.

3.00 CONSTRUCTION OF 10 FT X 12 FT SIZE OF 8'6" HEIGHT ROOM:

The firm shall arrange for construction of 10 ft X 12 ft size of 8'6" height room for RO Water plant system with Load bearing construction, PCC (1:4:8) leveling course, CM 1:5 CR Masonry foundation 4' height (2'below and 2'above GL), refilling basement with local soils and well compacted, CM 1:5 9" thick brick masonry, 4.5" thick RCC (1:2:4) slab, 3'6"x6' size MS door, 3'x4' UPVC windows with grill (2Nos), plastered with 12 mm CM(1:5) inside and outside, Painting the Internal and external walls with two coats of Emulsion paint over one coat of cement primer, Flooring with kadapa slab over 4" CC bed cost of all materials, labour charges, incidental charges, all leads and lifts etc., complete for finished item of work as directed by the Engineer in charge.

3.01 MODE OF PAYMENT: The payment shall be made on the basis of Sq.Ft. The measurement shall be made as per finished slab area.

4.00 SUPPLY, ERECTION, TESTING AND COMMISSIONING OF 1000 LPH REVERSE OSMOSIS (RO) WATER PLANT:

The firm shall arrange for Supply, erection, testing and commissioning of 1000 LPH Reverse Osmosis (RO) Water plant with all suitable equipment, material and instruments & controls like CRI make Raw Water Pump, CRI high pressure pump, membranes, Pressure Vessels, Filter media, carbon, multiport valve, jumbo housing, jumbo filter, membrane housing, flow meter, pressure guage, control panel, dosing pump, antiscalent, SS skid, 2000 litre capacity SS treated water storage tank, 2000 litre capacity PVC raw water storage tank, UPVC pipes and fittings, installation etc. The rate including cost and conveyance of all materials, pipe line connection from over head tank to RO plant and out let pipes with suitable tap arrangement, all labour, transportation, incidental charges, all leads and lifts etc., complete for finished item of work as directed by the Engineer in charge.

4.01 MODE OF PAYMENT: The payment shall be made on the basis of Job.

5.00 DRILLING OF 4" SIZE BORE WELL:

The firm shall arrange for Drilling of 4" size bore well with necessary casing pipe.

5.01 MODE OF PAYMENT: The payment shall be made on the basis of RFT.

6.00 SUPPLY, ERECTION AND TESTING OF 3 HP FIFTEEN STAGES SUBMERSIBLE PUMP:

The firm shall arrange for Supply, erection and testing of 3 HP fifteen stages submersible pump of approved make with necessary delivery pipes, control panel, submersible electrical cable etc. complete for finished item of work.

6.01 MODE OF PAYMENT: The payment shall be made on the basis of No's.

SCHEDULE - A

BILL OF QUANTITIES

- a) The quantities given in the bill of quantities are approximate but they are subject to alterations, omissions, deductions or additions as provided for in the conditions of this contract and do not necessarily show the actual quantities of work to be done. The unit rates noted below are those governing payment of extras or deductions for omissions according to the conditions of the contract as set forth in the preliminary specifications of the A.P. Standard Specifications and other conditions and specifications of this contract.
- b) It is to be expressly understood that the measured work is to be taken net (not withstanding any custom or practice to the contrary) according to the actual quantities when in place and finished according to the drawings or as may be ordered from time to time by the Engineer-in-charge and the cost calculated by measuring or weight at the respective prices without any additional charges for any necessary or contingent works connected therewith.
- c) For all items of work which are more than 10% in excess of the quantities shown in the bill of quantities the rate payable for excess quantities beyond 10% shall be either tender rate or the SS rate for the item plus or minus the overall tender percentage whichever is less. The SS rate means the rate within the estimate has been prepared for comparison with tenders.
- d) The rates quoted by the contractor are firm till completion of the work in all respects. No price variation of rates is allowed in case of delay in handing over of site to the contactors, if any by the department. However, corresponding extension of time will only be granted to the contactors.

SCHEDULE-A

Name of work: APSPCL - CSR - Supply, Erection, Testing and Commissioning of RO plant of 2000 lit/hr capacity including construction of plant room at Diguvagottivedu Village, Chinna Mandem Mandal of YSR Kadapa District, A.P.

S. No	Quan	itity	Description of Item	Rate	per	Amount
1	130.00	Sq.Ft	Construction of 10 ft X 12 ft size of 8'6" height room for RO Water plant system with Load bearing construction, PCC (1:4:8) levelling course, CM 1:5 CR Masonry foundation 4' height (2'below and 2'above GL), refilling basement with local soils and well compacted, CM 1:5 9" thick brick masonry, 4.5" thick RCC (1:2:4) slab, 3'6"x6' size MS door, 3'x4' UPVC windows with grill (2Nos), plastered with 12 mm CM(1:5) inside and out side, Painting the Internal and external walls with two coats of Emulsion paint over one coat of cement primer, Flooring with kadapa slab over 4" CC bed cost of all materials, labour charges, incidental charges, all leads and lifts etc., complete for finished item of work as directed by the Engineer in charge.		Sq.Ft	
2	1.00	Job	Supply, erection, testing and commissioning of 1000 LPH Reverse Osmosis (RO) Water plant with all suitable equipment, material and instruments & controls like CRI make Raw Water Pump, CRI high pressure pump, membranes, Pressure Vessels, Filter media, carbon, multiport valve, jumbo housing, jumbo filter, membrane housing, flow meter, pressure guage, control panel, dosing pump, antiscalent, SS skid, 2000 litre capacity SS treated water storage tank, 2000 litre capacity PVC raw water storage tank, UPVC pipes and fittings, installation etc. The rate including cost and conveyance of all materials, pipe line connection from over head tank to RO plant and out let pipes with suitable tap arrangement, all labour, transporation, incidental charges, all leads and lifts etc., complete for finished item of work as directed by the Engineer in charge.		Job	
3	300.00	RFT	Drilling of 4" size bore well with necessary casing pipe		RFT	

S. No	Quan	itity	Description of Item	Rate	per	Amount
4	1.00	No	Supply, erection and testing of 3 HP fifteen stages submersible pump of approved make with necessary delivery pipes, control panel, submersible electrical cable etc. complete for finished item of work		No	
					Total	
	In Words					

Contractor

Sd/-Superintending Engineer/Civil